

8	Supplying and Drawing 3 core Flat PVC Shalted Submersible Pump Cable Manufactured with Electrolytic Grade Copper with Flexible copper conductor to table 3 class 5 of IS 8130-1984 and Virgen PVC insulation and Sheated Suitable for working Voltage Upto 1100 Volts as per complete as per specifications.	Mtrs	1800.00	151.00	Rupees One Hundred Fifty One Only
9	Supplying and fixing 50mm Non Return Vavle of vertical type of approved make including cost of all materials labour HOM of equipment with all leads Complete as per Specification	Nos	3.00	1530.00	Rupees One Thousand Five Hundred Thirty Only
10	Supplying and fixing 50mm GM Gae Vavle Complete as per Specification	Nos	3.00	1430.00	Rupees One Thousand Four Hundred Thirty Only
11	Supplying and fixing 160mm Borewell cap with clampset Complete as per Specification	Nos	3.00	690.00	Rupees Six Hundred Ninety Only
12	Supplying and fixing 50mm GI Union Complete as per Specification	Nos	3.00	245.00	Rupees Two Hundred Forty Five Only
13	Supplying and fixing 50mm GI Elbow Complete as per Specification	Nos	3.00	120.00	Rupees One Hundred Twenty Only
14	Supplying and fixing 50mm GI collar Heavy duty Complete as per Specification	Nos	48.00	1350.00	Rupees One Thousand Three Hundred Fifty Only
15	Supplying and delivery at site brand new star / Essen / Lotus / Sun shines / Adharsh / GK Controls best indigenous make combined energy meter cum control panel board unit of size 1200x600x350mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3ph, 50 hz, 380/440 volts, AC supply with spring loaded latch, locking device with a key ribs should be provided inside the door canopy apron and louvers ventilators shall be provided the combined energy meter cum control panel board unit suitable for operation on 3ph, 50 hz, 380/440 volts AC supply shall be consists etc., complete the panel board shall be consist etc., complete the panel board shall be fabricated on single unit in the above componenets panel board for suitable pumpset with star delta staretr out door type 10hp to 15 hp Complete as per Specification	Nos	3.00	10000.00	Rupees Ten Thousand Only
16	Providing and fixing of 50mm G.I pipe 'C' class heavy duty foe erection of submersible pumpset Complete as per Specification	Mtrs	774.00	402.75	Rupees Four Hundred Two and Seventy Five Paise Only
17	Erection of combined panel board and meter unit with necessary materials and labour including providing cement concrete foundation bed cont door type etc., Complete as per Specification	Nos	3.00	475.00	Rupees Four Hundred Seventy Five Only

Signature of the Contractor (TM-2)

Executive Engineer